

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 22. NR. 9. W. .  
T 23 NR 9 W

----- Wexford ----- COUNTY

DESCRIPTION OF CORNER ..Section corner common to Sections 5-6-31-32 ..

DESCRIPTION OF CORNER MONUMENT ..1" pipe with a 4" brass cap. ....

WITNESSES TO CORNER ..7" Aspen .. N 88 W .. 43 1/2 links ..

\*30" W. Pine Stump .. S 73 E .. 11 links ..

\*34" W. Pine Stump .. S 53 W .. 59 1/2 links ..

-----  
\*OLD NBTs - PROBABLY TEED'S

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial retracement of this township. Found remains of very old post bottom, after considerable digging, supported by very old NBTs, which I conclude to be Delmore Teed's of 1900-1910. Hemlock government BTs all gone - but may have been in evidence at time corner was established.

Corner was placed and witnessed November 20, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*  
REGISTERED LAND SURVEYOR

DATE 11/26/58