

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22 NR. 9 W. . .

Wexford COUNTY

DESCRIPTION OF CORNER $1/4$ corner common to Sections 13 and 24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

10" R. Oak	-	N32W	-	41 $\frac{1}{2}$ links
6" W. Oak	-	N58E	-	55 $\frac{1}{2}$ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found good stake point at corner, at government bearing and distance form holes at the sites of the government BTs. Falls within 4 links of proportionate corner. Very probably the government corner.

Corner was placed and witnessed April 22, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 4/23/59
REGISTERED LAND SURVEYOR