

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 22 NR 9 W . . .

Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 13 and 14

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" R. Oak - N8E - 8 links  
8" R. Oak ⊕ N82W - 24 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial resurvey of this township. Corner was established by proportionate measurement between section corners. Could not make positive identification of corner, with only one government BT likely to be found. One possible point for gov't corner is 12 links east of our established corner. This point is faced, generally, by 2 pine stumps bearing three notches which could have been intended as witnesses, but could find no evidence of post after considerable digging. Many possible sites for government BT makes positive identification impossible.

Corner was placed and witnessed May 5, 1959.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting DATE 5/5/59  
REGISTERED LAND SURVEYOR