

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22. NR. 8. W. ---
T 22 NR 9 W

Missaukee-Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 6 and 1

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

| | | | | |
|-----------|---|------|---|----------|
| 7" R. Oak | - | N34E | - | 45 links |
| 8" R. Oak | - | S43E | - | 32 links |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a partial resurvey of this township. Could make no positive identification of government corner although one possible position would be about 15 links NW of our corner, based on a hole at the possible site of the NW gov't BT. Could find no evidence of post when digging here. It is also possible the NW BT could have been removed from a woods trail which passes through this area, just west of our corner. Good corner $\frac{1}{2}$ mile north and proportioned corner $\frac{1}{2}$ mile south.

Corner was placed and witnessed May 5, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 5/5/59
REGISTERED LAND SURVEYOR