

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


WEXFORD COUNTY
T 22 N R 9 W

DESCRIPTION OF CORNER E 1/16 corner common to Sections 22 - 27

CORNER MONUMENT Set 1"x36" pipe in E-W blacktop county road

DATE MONUMENT PLACED AND WITNESSED 4-19-71

WITNESSES TO CORNER..... Power Pole N 42 W 38.8'



8" Jack Pine S 9 E 58.0'

Cedar Post w/location tag Due N 33.0'

AND

Ctr. E-W Road Due S. 1.5'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established equidistant and on line between Sec. corner to East and 1/4 corner to West, while making a retracement survey in this area.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Carl F. Roney
REGISTERED LAND SURVEYOR

DATE

4-26-71

12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68