


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES  
  
LAND CORNER RECORD

WEXFORD COUNTY  
T 22 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 22-27  
 CORNER MONUMENT Set 1"x36" pipe in center of E-W blacktop county road  
 DATE MONUMENT PLACED AND WITNESSED 4-19-71  
 WITNESSES TO CORNER.....



Power Pole	N 34 W	111.9'
21" Maple	S 4 W	128.5'
AND		
Cedar post with location tag Due North		33.0'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a retracement survey in this area. The corner was set in line with old fence line to North and in Center of E-W road. This position fits A. J. Teed, deceased Wexford County Surveyor, survey of Sec. 27, dated 1891 and 1904. We recovered Teed's center of Sec. 27 and the N 1/4 of Sec. 27 is in line with the S 1/4 and center of Sec. 27. We also fit Teed's distance from the N 1/4 to the NE corner of Section 27. Teed's notes are in possession of Walt Fraser, RLS, Traverse City.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roer*  
REGISTERED LAND SURVEYOR

DATE

4-26-71

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

12028