

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY
T 22 N R 9 W


DESCRIPTION OF CORNER 1/4 corner common to Sections 24-25

CORNER MONUMENT Set 1"x36" pipe in E-W blacktop County Road

DATE MONUMENT PLACED AND WITNESSED 4-10-71

WITNESSES TO CORNER.....

<u>Power Pl.</u>	<u>N 40 W</u>	<u>40.0'</u>
<u>9" Oak</u>	<u>N 85 E</u>	<u>57.3'</u>
<u>7" Maple</u>	<u>S 16 E</u>	<u>30.8'</u>
<u>AND Ced. Post w/location tag</u>	<u>Due N</u>	<u>23.0'</u>
<u>Ctr. E-W Road</u>	<u>Due S</u>	<u>0.5'</u>



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished equidistant and on line between Section corners to E & W. while making a retracement survey in this area. The 1/4 corner lines up with the East edge of pine plantation to the North, which both adjoining land owners to North agree is the proper location for the N-S 1/4 line.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Carl F. Rover
REGISTERED LAND SURVEYOR

DATE

4-26-71

12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68