


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY
T 22 N R 9 W

DESCRIPTION OF CORNER Sec. corner common to Secs. 22-23-26-27
CORNER MONUMENT Set 1"x36" pipe in Center of E-W blacktop Co. Road
DATE MONUMENT PLACED AND WITNESSED 4-19-71
WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

<u>6" Red Pine</u>	<u>N 28 E</u>	<u>106.6'</u>
<u>6" Jack Pine</u>	<u>S 63 W</u>	<u>100.6'</u>
AND		
<u>Cedar Post with location tag Due N</u>		<u>33.0'</u>

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored in line with fence to North and South and in the center of E-W County Road. This position fits very close to a prorated U.S. distance for one mile N & S and fits survey measurements by A.J. Teed, deceased Wexford County Surveyor, for 1/2 mile West, Sec. 27., Highway survey dated September 16, 1904; and for one mile East, Sec. 26, Highway Survey dated March 31, 1905. Teeds survey records are in possession of Walt Fraser, RLS, Traverse City.

SURVEYOR'S SEAL

SIGNED

Carl F. Roer

DATE

4-26-71

DISTRIBUTION:

REGISTERED LAND SURVEYOR

12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68