

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD - *Missaukee* COUNTY


T 22 N R 8 & 9 W

DESCRIPTION OF CORNER Sec. corner common to Sections 24-25-19-30

CORNER MONUMENT Set Std. Dept. Nails 6" below road surface

DATE MONUMENT PLACED AND WITNESSED 4-16-71

WITNESSES TO CORNER..... 22" Oak N 84 E 66.5'



22" Oak S 52 E 109.5'

24" Oak S 17 E 132.0'

AND

Cedar post w/location tag DUE EAST 33.0'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found 2' piece of metal sign post and remains of wood stake, buried, in line with approximate center of County blacktop road to West and in line with Easterly edge of N-S gravel County Road. The corner as recovered agrees in description and location as described by Norm Sageman, former Wexford County Road Commission Engineer in 1958. The corner as recovered fits very close to a position by single proportion between recovered corners a mile North and South and also fits very close to U.S. distance to recovered Section corner one mile West.

SURVEYOR'S SEAL

SIGNED

Carl F. Rosen
REGISTERED LAND SURVEYOR

DATE

4-23-71

DISTRIBUTION:

12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68