


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY  
T 22 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 22-26  
 CORNER MONUMENT Set 1" x 36" pipe in E-W blacktop County Road  
 DATE MONUMENT PLACED AND WITNESSED 4-16-71  
 WITNESSES TO CORNER.....

<u>24" Maple</u>	<u>N 26 E</u>	<u>118.5'</u>
<u>16" Maple</u>	<u>S 6 E</u>	<u>82.4'</u>
<u>38" Maple (cluster of 3)</u>	<u>S 72 W</u>	<u>147.7'</u>
<u>AND Cedar Post w/location tag</u>	<u>Due North</u>	<u>33.0'</u>
<u>Old Fence remains North</u>	<u>Due East</u>	<u>12.0'</u>
<u>CIRCLE CORNER REGISTERED</u>	<u>Center E-W Road</u>	<u>Due North</u>
		<u>2.0'</u>



DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a retracement survey in this area. The corner was positioned on a straight line between Section corners a half mile to East and West and at a pre-rated distance to survey measurement by A.J. Teed, deceased Wexford County Surveyor. Survey for Highway dated March 21, 1905. Records in possession of Walt Fraser, RLS, Traverse City.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Carl F. Rozer*  
REGISTERED LAND SURVEYOR

DATE

4-23-71

12028

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68