


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY
T 22 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Secs. 26 & 35
 CORNER MONUMENT Set Std. Dept. Man buried in Gravel Road
 DATE MONUMENT PLACED AND WITNESSED 4-29-71
 WITNESSES TO CORNER.....

8" Twin Oak	N 27 W	58.4'
14" R. Pine	N 36 E	63.7'
12" Oak	S 47 E	37.22'
AND Cedar Post & location tag	Due W	33.0'



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored on the basis of Teed surveys in Sec. 35, dated 1881, 1886, 1891 and 1903. Teeds Center of Sec. 35 and South 1/4 Corner of Sec. 35 were recovered during MSND survey in 1966. The N 1/4 of Sec. 35 was restored during this survey by projecting a straight line Northerly from the S 1/4 of Sec. 35 through the Center of Sec. 35 and setting the N 1/4 of Sec. 35 on this line at double the distance from the center of Sec. 35 to the N 1/16 corner on the N-S 1/4 line. The 1/4 corner common to Secs. 26 & 35 by this method fits Teed's distances for 1/2 mile E-W & S reasonable, and fits the average line of County Road R.O.W. (old Twp rd) South.

SURVEYOR'S SEAL

SIGNED

Carl F. Roser

DATE

5-6-71

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68