


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY
T 22 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Secs. 26 & 27
CORNER MONUMENT Set Std. Dept. Non & Cedar Guard post by found stake
bottom and USBT stump.
DATE MONUMENT PLACED AND WITNESSED 4-30-71
WITNESSES TO CORNER..... 18" Maple N 75 W 60.4'



36" W. Pine stump N 36 W 41.9'
30" W. Pine stump N 11 E 53.0'

AND

All standing timber damaged by recent fire.

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found definite shadow of two stake bottoms, one probably US and the other Teed's, from USBT stump SW. The 1/4 corner as recovered fits the splitup of Sec. 27 by Teed in 1885, 1887, 1891 and 1904.

SURVEYOR'S SEAL

SIGNED Carl F. Roser DATE 5-6-71
REGISTERED LAND SURVEYOR
12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68