

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD-MISSAUKEE COUNTY


T 22 N R 069W

DESCRIPTION OF CORNER 1/4 corner common to Sess. 25 & 30

CORNER MONUMENT Set Std. Dept Mon buried in W edge of N-S dirt Co. rd.

DATE MONUMENT PLACED AND WITNESSED 4-20-71

WITNESSES TO CORNER..... 12" Oak N 25 W 48.0'



9" Oak N 53 E 97.2'

Cedar Post w/location tag Due W 38.0'

AND

Ctr. of N-S dirt road Due E 9.0'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished equidistant and on line between Section corners to North and South, while making a retracement survey in this area. The corner as set is in line with vague fence remains to the West.

SURVEYOR'S SEAL

SIGNED

*Carl F. Boxer*

DATE

4-27-71

DISTRIBUTION:

REGISTERED LAND SURVEYOR **12028**

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68