


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY
T 22 N R 9 W

DESCRIPTION OF CORNER E 1/16 corner common to Sections 27 - 34
CORNER MONUMENT Set 1"x36" pipe in E-W blacktop county road.
DATE MONUMENT PLACED AND WITNESSED 4-30-71
WITNESSES TO CORNER..... 22" Oak N 6 E 106.50



5" Scotch Pine S 41 E 81.20'
Cedar Guard post & location tag Due N 33'
Centerline E-W B.T. county road Due S 2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established equidistant and on line between Sec. corner to East and 1/4 corner to West, while making a retracement survey in this area. The corner falls in approximate line with fence remains (mostly down) to South.

SURVEYOR'S SEAL

SIGNED

Carl F. Roser

DATE

5-6-71

DISTRIBUTION:

REGISTERED LAND SURVEYOR **12028**

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68