


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD-NISSAUKEE COUNTY
T 22 N R 8 6 9 W

DESCRIPTION OF CORNER Sec. corner common to Secs 25-26-30-31
CORNER MONUMENT Found 1 1/2" x 18" pipe buried in W edge of N-S dirt road,
in line with old fence remains to West.
DATE MONUMENT PLACED AND WITNESSED 4-29-71

WITNESSES TO CORNER.....	<u>18" Oak</u>	<u>N 46 W</u>	<u>95.2'</u>
	<u>8" Oak</u>	<u>S 41 W</u>	<u>101.8'</u>
	<u>18' Oak</u>	<u>S 76 E</u>	<u>95.1'</u>
	AND Cedar post w/location tag Due E		<u>33.0'</u>
	Ctr. N-S dirt road Due E		<u>7.0'</u>



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Recovered corner as found by MSND in 1966, which is the corner as recovered and monumented by John McBain in October 1906. McBain set a 1 1/2" x 18" pipe from U.S. witness SW.

SURVEYOR'S SEAL

SIGNED

Carl F. Roper
REGISTERED LAND SURVEYOR

DATE

5-6-71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

12028

R 4047
Rev. 10/68