

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES


LAND CORNER RECORD

WEXFORD

COUNTY

T 22 N R 9 W

DESCRIPTION OF CORNER E 1/16 corner common to Sections 25 & 26 36  
Set 1"x36" pipe & Cedar Guard Post w/location tag  
 CORNER MONUMENT 4-20-71  
 DATE MONUMENT PLACED AND WITNESSED  
 WITNESSES TO CORNER.....



10" Maple	N 51 W	53.7'
9" Maple (cluster of 4)	N 14 W	70.4'
24" W. Pine stub 12' High	S 8 E	49.8'
AND E-W fence remains	Due N	4'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

**This corner was established equidistant and on line between Sec. corner to East and 1/4 corner to West, while making a retracement survey in this area.**

SURVEYOR'S SEAL

SIGNED

*Carl F. Roser*  
REGISTERED LAND SURVEYOR 12028

DATE

4-27-71

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68