

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY


T 22 N R 9 W

DESCRIPTION OF CORNER Sec. corner common to Sections 25-26-35-36

CORNER MONUMENT Set Std. Dept. Mon & Cedar Guard post by recovered Squared Cedar Post.

DATE MONUMENT PLACED AND WITNESSED 4-29-71

WITNESSES TO CORNER..... 12" R. Pine S 81 E 35.1'



16" R. Pine N 72 W 62.0'

14" R. Pine N 14 W 59.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found squared cedar post in line with old fence remains to E & W and on average center line of old Twp. road R.O.W. (old RW fences) for one-half mile to South. This corner was recovered by the MSHD in survey for M-55 in 1966. The corner fits Teed distance for one-half mile South and Teed and U.S. distance for 1/2 mile West.

SURVEYOR'S SEAL

SIGNED

*Carl F. Rorer*

DATE 5-6-71

REGISTERED LAND SURVEYOR

12028

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68