

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>22</u> N. <u>9</u> R. <u>9</u> W.	<u>G-2;</u> ✓
2. PROPERTY CONTROLLING IN SECTION <u>3</u>	T. <u>22</u> N. <u>9</u> R. <u>9</u> W.	<u>5; 6;</u> ✓
3. MISCELLANEOUS PROPERTY IN SECTION <u>2</u>	T. <u>22</u> N. <u>9</u> R. <u>9</u> W.	<u>117.6'-W of J-3</u>
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 27, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on December 27, 1985, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (Continued):

5	6
Drove 5/8" x 34" Rerod w/RLS cap & set cedar post w/loc tag	Drove 5/8" x 34" rerod w/RLS cap & set cedar post w/loc tag
17" Oak S46°E 8.4'	8" White Pine S74°E 80.3'
14" Oak S26°W 11.8'	6" White Birch N40°W 4.8'
8" White Pine N40°W 29.5'	6" Oak N12°E 27.7'
Cor. falls on top of N-S ridge	Corner falls at N. edge of grassy marsh area

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 117.6'-W of J-3 - Wit. cor. to S $\frac{1}{4}$ cor. Sec. 2. Previous Dept. cor. of Record (KJO-1958). KJO fd. Teed cor. (1901) who had Govt. B.T.s.
 - G-2 - Restored $\frac{1}{4}$ cor. to Sections 3&4 on line & double distance across recovered Teed ctr. of Sec. 4 & recovered Teed E 1/8 cor. on E-W $\frac{1}{4}$ line of Sec. 4. Fits Teed's N.B.T.(stp) remains. Teed's notes, June 3, 1901 indicate he had both Govt. B.T.s & he ran the E-W & N-S $\frac{1}{4}$ lines of Sec. 4.
 - 5 - Estab. SW cor. of frl NW $\frac{1}{4}$ of frl. NE $\frac{1}{4}$ of Sec. 3 per std. B.L.M. instructions (run-out Sec. - prorated to G.L.O. plat).
 - 6 - Estab. NW of Govt. Lot 1 of Sec. 3 per std. B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

117.6'-W of J-3	G-2
Found Department monument	Set DNR mon. & cedar post per Co. surveyor Teed (1901)
6" Red Oak N15°W 70.5'	9" Maple N58°E 52.3'
2" White Pine S40°W 49.7'	8" Triple Maple S14°W 42.2'
8" Red Oak Due W 50.7'	7" Beech N70°W 19.7'
Dept. Mon. (S $\frac{1}{4}$, S-2) S89°23'E 117.6'	4" Oak N16°E 46.4'
W. edge of pond East 20'±	Fd.Wex.Co.Mon.
	J. Nelson N11°50'48"W 65.32

SIGNED BY Carl F. Roser 01-24-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

WEXFORD COUNTY

