

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 22 N. R. 9 W.	F-5; G-4; G-5;
2. PROPERTY CONTROLLING IN SECTION	9, T. 22 N. R. 9 W.	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 3, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a

Decree of a Court of law:

C. (Continued):

xxxx Description of corner evidence found and/or method applied in restoring or re-establishing corner:		
<u>G-5</u>	<u>3</u>	
Fd. 5/8" rerod in Monument box	Drove 5/8" x 34" rerod w/RLS cap & set cedar post w/loc tag	
5" Red Pine S07°E 62.44'	4" White Pine S04°W 14.8'	
T. Pole S30°E 66.38'	18" Maple S56°W 29.8'	
7" Red Pine N04°W 70.18'	4" White Pine N02°W 22.4'	
8" White Pine N42°W 84.47'	Ctr. R.R. tracks East 59'±	
	N-S Tr. Road West 70'±	

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- F-5 - Fd. Wex. Co. Mon. in ctr. of US-131; Bit. surface, believed to be over 1925 conc. pavt. Mon. fits Dept. survey data 1/2 mile E&W (KJO-1958).
 - G-4 - Restored 1/4 cor. comm. to Sections 9&10 mid-way & on line between Sec. corners to N&S. Fits E-W 1/4 line in Sec. 9 (Teed ctr. & Govt. W 1/4 Cor.) & E-W 1/4 line in Sec. 10 (KJO ctr. & Teed E 1/4 cor.).
 - G-5 - Fd. 5/8" rerod in mon. box; 1.5'± N. of ctr. of old E-W B. top rd. Dept. survey (KJO-1958) shows R.R. spk. here in line with fn. N&S; fn. S. still evident. Mon. box fits KJO distances E&W 1/2 mile.

3 - Drove 5/8" x 34" rerod for NW cor. of SW 1/4-NW 1/4 of Sec. 9; mid-way & on line bet. Sec. Cor. N. & 1/4 Cor. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>F-5</u>		<u>G-4</u>
Fd. Wex. Co. Mon., flush w/B. top	Set Wexford Co. mon. & cedar post	
Power Pole S72°E 96.28'	3" Red Pine N50°W 16.9'	
Power Pole S60°W 123.15'	8" Sugar Maple N55°E 6.9'	
13" Apple N46°W 112.90'	16" Sugar Maple S35°E 11.3'	
5" Elm N50°E 117.89'	5" Red Pine S25°W 34.8'	
	Cor. of old fn. & rows of trees W'ly & S'ly is N05°23'E 48.7'	

SIGNED BY Carl F. Roser 01-24-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ WEXFORD COUNTY