

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>22</u> N. <u>0.</u> , R. <u>9</u> W. <u>0.</u>	J-4; J-5; K-4;
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	, T. <u>22</u> N. <u>0.</u> , R. <u>9</u> W. <u>0.</u>	4
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 9, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (Continued):

<u>K-4</u>	<u>4</u>
Fd. $\frac{1}{2}$ " x 18" iron rod; added Wexford Co. Mon. & cedar post	Drove $\frac{5}{8}$ " x 34" rerod w/RLS cap & set cedar post w/loc tag
16" Red Oak N27°W 87.0'	3" Maple (clip 2) N55°W 17.8'
*16" Red Pine N80°W 48.8'	3" Maple N50°E 20.6'
*13" Red Pine S41°W 83.8'	4" Red Oak S55°E 24.9'
Ctr. dirt rd. NW & SE Due W 26'	3" Red Oak S10°W 11.5'

* = KJO 1958 B.T.s

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- J-4 - Estab. ctr. of Sec. 11 at intersection of $\frac{1}{4}$ lines.
 - J-5 - Previous Dept. Corner of Record (KJO-1958).
 - K-4 - Fd. $\frac{1}{2}$ " x 18" rod that fits previous Dept. Cor. wits (KJO-1958).
 - 4 - Drove $\frac{5}{8}$ " x 34" rerod for NE cor. of SW $\frac{1}{4}$ of NW $\frac{1}{4}$ of Section 11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>J-4</u>	<u>J-5</u>
Drove $\frac{5}{8}$ " x 34" rerod w/RLS cap & set cedar post w/loc tag	Fd. Dept. mon. in ctr. E-W trail
2" Red Oak N20°W 32.3'	4" Maple N15°E 12.7'
5" Red Oak N50°E 11.0'	8" Maple S25°E 20.0'
3" White Pine S30°E 10.3'	3" White Pine S35°W 38.1'
	Set cedar post w/loc tag Due N 16 $\frac{1}{2}$ '


SIGNED BY Carl F. Roser 01-24-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ WEXFORD COUNTY