

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>11</u> , T. <u>22</u>	N. <u>8.</u> E. _____ S., R. <u>9</u> W.	✓ ✓ ✓ ✓ <u>8:11:12:13</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ E. _____ S., R. _____ W.	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 9, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (Continued):

<u>12</u>	<u>13</u>
Drove 5/8" x 34" rerod w/RLS cap & set cedar post w/loc tag	Drove 5/8" x 34" rerod w/RLS cap & set cedar post w/loc tag
43" Red Oak N65°W 83.06'	8" Maple (clp 5) N70°W 12.5'
30" Red Oak S75°E 109.45'	17" Red Oak (clp 2) N20°E 7.0'
43" Red Oak S20°E 84.80'	3" Red Oak N85°E 22.5'
Ctr R.R. tracks Due S 119'	Ctr R.R. tracks Due N 166'
Ctr E-W dirt rd. Due N 50'	

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 8 - Drove 5/8" x 34" rerod for SE corner of SW $\frac{1}{4}$ of NW $\frac{1}{4}$ of Section 11.
 - 11 - Drove 5/8" x 34" rerod for SE cor. of NW $\frac{1}{4}$ of SW $\frac{1}{4}$ of Section 11.
 - 12 - Drove 5/8" x 34" rerod for NE corner of SE $\frac{1}{4}$ of SW $\frac{1}{4}$ of Section 11.
 - 13 - Drove 5/8" x 34" rerod for SW corner of NE $\frac{1}{4}$ of SE $\frac{1}{4}$ of Section 11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>8</u>	<u>11</u>
Drove 5/8" x 34" rerod w/RLS cap & set cedar post w/loc tag	Drove 5/8" x 34" rerod w/RLS cap & set cedar post w/loc tag
10" White Oak N05°W 13.1'	9" Red Pine N55°E 98.6'
3" Red Pine S15°E 37.6'	7" Black Cherry (clp 4) S55°E 95.3'
3" Red Pine S40°W 47.3'	10" Black Cherry S60°W 57.7'
	Ctr. dirt rd. intersection S20°E 96'

SIGNED BY Carl F. Roser 01-24-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ WEXFORD COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET