

MAY 20 1977

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1996 DEC 10 PM 4:04

For corners in WEXFORD (County)

Located In:

Corner Code #

- 1. Public Land Survey T 22N R 9W G-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

Linda Lougheed Miller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at row 13, column G.

I, CRAIG J. PULLEN, in a field survey on OCTOBER 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-13 1837 ORIGINAL GLO SURVEY BY J. BRINK WOOD POST WHITE PINE 12 N72 1/2 E 62 YELLOW PINE 10 N61W 14 1872 MITCHELL'S REVISED PLAT OF THE VILLAGE OF CLAM LAKE (NOW CITY OF CADILLAC) BY R. MCCLAIN 1881 MAY & MITCHELL'S ADDITION TO THE CITY OF CADILLAC, SEC.33, T22N, R9W BY A.J. TEED 1884 G.A. MITCHELL'S PLAT OF THE SE 1/4 SEC.33, T22N, R9W BY A.J. TEED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- G-13 FOUND 3" CLAY TILE IN CONCRETE ON LINE WITH IRONS FOUND ON THE LINE COMMON TO MAY & MITCHELL'S PLAT AND G.A. MITCHELL'S PLAT OF THE SE 1/4, AND 66' SOUTH OF IRONS FOUND ON THE NORTH LINE OF DIVISION ST. SET 5/8" IRON WITH BRASS CAP IN CENTER OF CLAY TILE. DISTANCE TO NW CORNER OF MAY & MITCHELL'S PLAT IS 1313.08' (1312.30'-P) AND TO THE S 1/4 CORNER SEC.34, T22N, R9W IS 2624.45'-M (2621.00'-P). THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved

Date: 10 Dec 96
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13 SECTION CORNER COMMON TO SECTIONS 33 AND 34, T22N, R9W, AND SECTIONS 3 AND 4, T21N, R9W 5/8" IRON WITH BRASS CAP IN 3" CLAY TILE IN CONCRETE. BRASS CAP STAMPED: 33, 34, 3, 4, 1996, CJP, 39095
N21°E 28" MAPLE 56.00'
S45°E NW CORNER HOUSE #114 56.65'
S84°W POWER POLE 62.68'
N41°W LIGHT POLE 80.06'
N53°W TOP CENTER FIRE HYDRANT 24.85'



Signed by Craig J. Pullen
Surveyor's Michigan License No. 39095

DECEMBER 10, 1996