

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Wexford  
 (County)

Located In:

Corner Code #

- |                                      |   |            |   |           |             |
|--------------------------------------|---|------------|---|-----------|-------------|
| 1. Public Land Survey                | T | <u>22N</u> | R | <u>9W</u> | <u>L-13</u> |
|                                      | T | _____      | R | _____     | _____       |
|                                      | T | _____      | R | _____     | _____       |
|                                      | T | _____      | R | _____     | _____       |
| 2. Property Controlling in Section   | S | _____      | T | _____     | _____       |
|                                      | S | _____      | T | _____     | _____       |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | _____       |
|                                      | S | _____      | T | _____     | _____       |

**RECEIVED**  
 1996 DEC 13 PM 3:32  
*Linda Loeschmiller*  
 WEXFORD COUNTY, MI  
 REGISTER OF DEEDS  
**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, George D. Smith, in a field survey on August 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-13) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Maple 12-N 54°E-41, Hemlock 16-N 41°W 36  
 1966 MSHD Gov't Witness record by C. Roser PS 12028 Liber 2, page 841, Set 3/4" Pipe 1/2 way and on straight line between found corners to East and West corner is in line with fence to South, P.P. N 16°W-60.92', 7" Red Pine S 55°W-62.26', Northwest corner of 11SC S 34°W 144.20', Northwest corner garage S 07°E 99.13' Centerline M-55 North 1.67'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-13) Found 3/4" Pipe set by Roser RLS #12028. This corner is accepted as a careful and faithful re-establishment of the position of the original corner being the 1/4 corner common to Section 36, T22N, R9W and Section 1, T21N, R 9W.

**SURVEY & REMONUMENTATION**

MAY 29 1997

**COMMISSION**

Peer Group Reviewed and Approved

Date: 14 Nov 96  
*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-13) Set Wexford Co. Brass Cap stamped S 1/4 36, 1996 PS#39098 on existing 3/4" pipe.  
 S5°W - 72.54' - Top Center R/W Marker  
 S3°E - 99.54' - NW Corner Foundation of Gar.  
 N21°E - 73.68' - P.Pole  
 N29°W - 64.07' - Pk. nail in West end CMP Culvert



Signed by George D. Smith  
 Surveyor's Michigan License No. #39098

Date 11-21-96