

APR 16 1999

RECEIVED

1998 DEC 30 PM 2:11

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>09W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, George D. Smith, P.S., in a field survey on April 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-3) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor. Yellow Pine 13-S16W-48; Yellow Pine 14-N56W-58
- M-3) 1883 A.J. Teed Survey Liber 1, Page 120. Corner found no description or witnesses given. Distance to East 1/4 corner measured 39.84.
- M-3) 1958 K. Ostling, PS #10068. LCRC Liber 2, Page 945. Set corner by proportionate measure between Section corner 1 mile south and town corner 1 mile north, set 1" pipe with brass cap, 6" oak S75°W 37.29' 20" oak, S44°E 60.39' 16" oak, N46°E 29.04'.
- M-3) 1982 J. Ray, PS #25869. Certificate of Survey Liber 1, Page 944. Found 1" pipe with brass cap, S75°W 57.30 6" oak, S44°E 60.40' 20" oak, N46°E 29.00' 15" oak. Distance to east 1/4 corner measured 2624.25'.
- M-3) 1986 J. Ray, PS #25869. Certificate of Survey, Liber 2, Page 188. Found 1" pipe witnesses the same as 1982 certificate of survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-3) Found DNR monument and 1 witness from 1958 Ostling PS #10068 L.C.R.C. This corner is accepted as a careful and faithful re-establishment of the position of the original corner being the section corner common to Section 1 and 12, T22N, R9W, and sections 6 and 7, T22N, R8W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3
DNR monument (1" pipe with brass cap)
West 37.25' 12" Oak (37.29' Ostling)
N20W 12.02' 5" Oak
N60E 29.31' 18" Oak
S35W 4.03' 3" W. Pine

Peer Group Reviewed and Approved

Date: 4 December 1998
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by George D. Smith
Surveyor's Michigan License No. 39098



Date 12-9-98