

**SURVEY & REMONUMENTATION**

**RECEIVED**

1993 DEC 29 AM 9:40

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

MAR 8 1 1994

For corners in

*Linda Laughmiller*  
**WEXFORD COUNTY, MI**  
**REGISTER OF DEEDS**

Wexford (County)	COMMISSION	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>9W</u>	<u>M-5</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- M-5) 1837 GLO Section post by John Brink, Deputy Surveyor, Pine 11" S 45° W 7, Pine 11" N 7° W 32
- M-5) 1853 GLO Section post by John Brink, Deputy Surveyor, Y. Pine 10" S 67 3/4° E 24, W. Pine 8" N 29 3/4° E 39, T22N, R8W
- M-5) 1883 Teed, Book 66, page 20 - good stake, Liber 1, page 132, S. from S. railroad 28'-9", Norway stump 10" S 8 3/4° W 30 1/2, W. Pine 16" S 21 1/2° E 65'-2"
- M-5) 1958 Ostling survey in Section 12, Liber 2, page 944
- M-5) 1987 Ray survey in Section 12, DNR monument 28' South of railroad grade, S 40° E Clump 12" Maple 33.93, N 70° E 6" Oak 42.40, N 50° W 6" Oak 71.75, West 6" Cherry 90.98

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


- M-5) Section corner common to Sections 12 and 13 and 7 and 18, T22N, R8W  
 Found DNR monument by 4th class Oak clump and ±29' South of centerline of an East-West old railroad grade. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93  
*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- M-5) DNR monument, Found 1" pipe with standard MDNR monument  
 S 35° E - 33.91 - Clump 12" Maples  
 N 77° E - 42.19 - 6" Oak  
 N 36° W - 71.76 - 6" Oak  
 N 76° W - 91.01 - 6" Cherry



Signed by *Richard D. Wilcox* Date 11/29/93

Surveyor's Michigan License No. 33989