

MAR 3 1994

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 9:40

*Linda Longmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

For corners in

Wexford (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 9W	M-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-6) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, W. Pine 36" N 75° W 73, W. Pine 26" S 35° W 19
- M-6) 1958 MDNR survey in Section 13: Set corner by proportionate measure, 1" pipe w/ 4" brass cap 4" below surface, 9" W. Oak N 85° W 42 links, 10" R. Oak S 61° E 39 1/2 links
- M-6) 1971 Roser survey in Section 13, Liber 2, page 943
- M-6) 1978 Wilcox survey in Section 13, Liber 1, page 643
- M-6) 1987 Ray survey in Section 13, Liber 65, page 143

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-6) 1/4 Section corner common to Sections 13, and 18, T22N, R8W  
Found DNR monument ±5' West of centerline of a North-South road and on West edge of a North-South road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6) Standard DNR monument on 1" pipe  
N 81° W - 144.1 - 17" Red Pine to blaze  
N 40° W - 145.1 - 24" White Pine to blaze  
S 57° E - 26.19 - 14" Oak  
N 34° E - 52.28 - 7" Oak  
S 25° W - 32.94 - 2" White Birch  
East 33.00 - Cedar post w. tag



Signed by *Richard D. Wilcox* Date 11/29/93

Surveyor's Michigan License No. 33989