

SUBJECT
REMONUMENTATION

MAR 5 1993

RECEIVED

LAND CORNER RECORDATION CERTIFICATE 1993 DEC 29 AM 9:40

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

<u>Wexford</u> (County)	Located In:	Corner Code <u>M-7</u>
1. Public Land Survey	T <u>22N</u> R <u>9W</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Wilcox, in a field survey on November 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-7) 1838 GLO Section post by John Brink, Deputy Surveyor, Tamarack 10° S 11° W 33, Hemlock 10° N 58° W 48.
- M-7) 1853 GLO Section post, Tamarack 10° S 83° E 18, Tamarack 12° N 74° E 38, T22N, R8W
- M-7) 1958 MDNR survey, Found stake and possible 2 bearing trees, set 1" pipe w/ brass cap
- M-7) 1965 USFS survey in Section 13: 1" pipe w/ 4" brass cap, 7" W. Birch N 40° W 65 1/2 links, 9" Poplar S 62° W 54 1/2 links, 18" boulder N 20° W 30 links
- M-7) 1971 Roser survey in Section 13, Liber 1, page 42
- M-7) 1978 Wilcox survey in Section 13, Liber 1, page 643
- M-7) 1987 Ray survey in Section 13, Liber 65, page 143
- M-7) 1990 Finnerty survey in Section 13, Liber 69, page 627

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- M-7) Section corner common to Sections 13, 24, and 18, 19, T22N, R8W
Found DNR monument with old cedar stake post in Tag Alder & Tamarack swamp. Corner is ±225' South of railroad grade running N 65° E or S 65° W and ±400' West to same railroad grade. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-7) Standard DNR monument on 1" pipe
N 58° W - 96.95 - 14" Maple
N 14° W - 93.16 - 20" Maple
N 14° W - 19.50 - Easterly side 12" x 24" pointed rock flush w/ ground
S 78° E - 52.44 - 3" Tamarack



Signed by *Richard D. Wilcox* Date 11/29/93
Surveyor's Michigan License No. 33989