

REMOVED

MAR 8 1993

COMMISSION

RECEIVED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC 29 AM 9:41

For corners in

Wexford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 22N R 9W M-8
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Linda Longmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-8) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor
Hemlock 11" S 14 1/2° W 40, Maple 9" N 5 1/2° W 20
- M-8) 1971 Roser survey in Section 24: DNR monument, 24" Oak N 32° W 100.5, 14" Oak S 89° W 95.1
18" Oak, N 12° E 16.1 (Liber 2, page 980)
- M-8) 1990 Wade-Trim Granger survey: Liber 69, page 664, DNR monument East 22" Oak 2.9',
S 80° W 5" Maple 14.75, North 20" Oak stump 17.05, S 25° W 8" Maple 5.22'
- M-8) 1990 Finnerty survey: Liber 69, page 627, DNR monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-8) 1/4 Section corner common to Sections 24, and 19, T22N, R8W
Found DNR monument ±58' West of centerline of a North-South road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved
Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8) Standard DNR monument on 1" pipe
S 69° E - 2.90 - 22" Oak
S 78° W - 14.80 - 5" Maple in clump
N 15° E - 17.05 - 20" Oak stump
S 25° W - 5.16 - 8" Maple in clump
N 29° W - 100.88 - 30" Oak
N 89° W - 95.44 - 16" Oak
N 15° E - 17.05 - 20" Oak stump



Signed by *Richard D. Wilcox* Date 11/29/93
Surveyor's Michigan License No. 33989