

MAR 3 1 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 9:42

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 22N R 9W M-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-11) 1838 GLO Section post by John Brink, Deputy Surveyor, Y. Pine 18" S 13° W 40, Birch 19" N 65 1/2 W 68
- M-11) 1853 GLO Section post by John Brink, Deputy Surveyor, W. Pine 26 N 16° E 25, W. Pine 15 S 61 1/2° E 26, T22N, R8W
- M-11) 1971 Roser survey in Section 25: Liber 2, page 973, 1 1/4" x 18" pipe, recovered corner as found by MSHD in 1966, which is the corner as recovered and monumented by John McBain in October 1906, McBain set a 1 1/4" x 18" pipe from U.S. witness SW, 16" Oak N 46° W 95.2, 8" Oak, S 41° W 101.8, 18" Oak S 76° E 95.1, Cedar post with loc. tag East 33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-11) Section corner common to Sections 25, 30, 31 and 36, T22N, R8W
Found bent 1/2" rerod in 1 1/4" I.D. iron pipe (pulled rerod) pipe 1.5' deep. Corner is ±8.8' West of centerline of a North-South road and in the centerline of a down fence to the West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved


Date: 11-29-93

Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" Iron with Wexford Co. brass cap stamped: SE 25, PS 33989, 1993
M-11)

- N 44° W - 95.24 - 20" Oak
- S 41° W - 102.42 - 10" Oak
- S 75° E - 95.83 - 18" Oak
- S 88° E - 33.00 - To face of location tag in cedar post
- East ± 8.80 - Centerline of North-South gravel road
- S 69° E - 48.87 - 8" Tri-Maple



Signed by *Richard D. Wilcox* Date 11/29/93

Surveyor's Michigan License No. 33989