

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford (County)	Located In	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>9W</u>	<u>K7</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 3, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		6		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:**
- K7-GLO - Set post - V.W. Caukin - 1852
W. Pine 14° N 52° E 22 L.
W. Pine 24° S 49° W 50 L.
 - C.F. Roser - 1971 - Found standard Dept. (DNR) Mon. - set cedar post - 9° Oak N 20° W 32.9'; 18° Oak S 71° W 11.8'; 8° Maple S 2° E 41.1'
 - K. J. Ostling - 1959 - FND ¼" pipe at corner w/ stp's. in place for both Gov't BT's. Found very old stake pt. also, when setting corner, which could likely have been set by Teed to restore corner 40-50 years ago. 8° R. Oak N 21° W 49.5 L.
14° R. Oak S 70° W 18 L., 6° Maple S 4° E 62.5 L.
 - LCRC L.2 P. 772 - J.L. Wilcox - 1975 - DNR 1" Iron & Cap - S 65° W 12.28' 18" Oak, N20° 33.25' 8" Oak, N70° W 26.00' 20" Oak.
 - Rec. Survey - L. 1, p. 644-1978 - found DNR Mon.

- B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**
- K7 - Section corner common to Sec. 13, 14, 23 & 24 - found 4" DOC (DNR) brass cap on 1" iron pipe of record. NNE-SSW 2-track is 10' E. DOC Monument accepted as a careful & faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- K7- 4" brass cap on 1" iron pipe
SE 0.9' to face cedar post found
Set blue carsonite post 1' S
*S 70° W 11.78' to set N & T in SE side 24" R. Oak (JLW, CFR, KJO)
*S 4° E 41.28' to set N & T in E side 13" R. Maple (KJO, CFR)
N 36° E 26.04' to fd. nail in W side UP
N 20° E 58.35' to set N & T in W side 13" R. Oak
N 53° W 102.65' to set N & T in SW side 3" W. Pine

* Old side nail above ours



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 1/3/2000