

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 24 T 22N R 9W 1
S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 3, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1- Rec. Survey- L. 1, p. 643 - J.L. Wilcox - 1978

- Set 1/2" Iron Rod
- 12" Oak N 72° W 23.12'
- 10" Oak S 30° E 25.80'
- 10" Oak N 32° E 17.33'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

1- W 1/16 corner common to Sec. 13 & 24 - found PS cap # 14102 on 1/2" iron rod per record survey. Fits SP position. Capped iron accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1- P.S. Cap #14102 on 1/2" Iron Rod.
- East 32.55' to capped iron rod #14102
- West 33.51' to capped iron rod #14102
- N 37° E 17.24' to FD. nail in E side 14" Tw. R. Oak (JLW)
- N 74° W 23.09' to FD. nail in N side 16" R. Oak (JLW)
- S 22° E 25.71' to FD. nail in SW side 13" R. Oak (JLW)
- Set blue carsonite post with location tag 1' S.



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 1/3/2000