

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford Located In _____ Corner Code # _____
(County)

1. Public Land Survey		T <u>22N</u>	R <u>9W</u>	L <u>7</u>
		T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____
3. Miscellaneous Property in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 3, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p><u>L7</u>-GLO - Set 1/4 post - V.W. Caukin - 1852 Y. Pine 16" N 17° E 15 L. Y. Pine 16" S 24° W 17 L.</p> <p>-K. J. Ostling - 1959 - FND. Good stake point at Gov't bearing and dist. From holes at sites of GLO BT's. Falls within 4 links of SP corner. Very probably the government corner. -Set 1" pipe with 4" brass cap. 10" R. Oak N 32° W 41.5 L. 6" W. Oak N 58° E 55.5 L.</p>	<p>-LCRC L.2, P. 772 - J.L. Wilcox - 1975 - DNR Monument -N 45° E 36.88' 6" Oak, S 30° W 46.65' 10" Oak, West 37.80' 12" Oak</p> <p>-Rec. Survey L. 1, p. 649 - DNR Mon. found - 1978 -Rec. Survey L. 65, p. 143 - DNR Mon. found - 1978</p>
--	--

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L7 - 1/4 corner common to Sec. 13 & 24 - found 4" DOC (DNR) brass cap on 1" iron pipe per Ostling and Wilcox. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L7- 4" brass cap on 1" iron pipe
Add blue carsonite post 1' S
West 2.30' (2.35'-R) to 1/2" Rebar at Parcel Corner
N 9° E 45.10' to set N & T in W. side 12" W. Pine scribed 'XBT'
S 87° E 36.91' to set N & T in N side 12" Tw. R. Oak scribed 'XBT'
S 10° W 91.05' to set N & T in E side 5" R. Pine scribed 'XBT'
S 80° W 37.78' to set N & T in S side 17" R. Oak (JLW)



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 1/3/2000