

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 (County) _____

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 9 T 22N R 9W 3
 S 9 T 22N R 9W 5

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Craig W. McVean, in a field survey on April 12, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

3 - **1986** - LCRC - Carl F. Roser - Set 5/8" x 34" rerod w/ RLS cap & set Cedar post with location tag, per Standard BLM procedure. 5 - None

1) W. Pine 4" S4°W 14.8'
 2) Maple 18" S56°W 29.8'
 3) W. Pine 9" N2°W 22.4'
 Center RR tracks East 59'±
 N-S Tr. Road West 70'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

3 - N 1/16 Cor. common to Sections 8 & 9 - T22N, R9W Found 5/8" capped iron rod #12028 with cedar guard post with location tag 1' NE. West 72' to centerline N-S trail and East 58' to centerline RR tracks. 5 - CN 1/16 Cor. Section 9, T22N, R9W - Set stamped 2" aluminum cap on 5/8" x 6' rebar per Standard BLM . 5' north to north edge of bog.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3 - Fd. 5/8" x 34" capped iron rod #12028 N82°E 26.87' to set Nail & Tag in S. side 10" W. Pine N56°W 46.85' to set Nail & Tag in N. side 12" W. Pine N5°W 22.52' to set Nail & Tag in W. side 16" W. Pine (#3) East 58' to Center RR tracks West 72' to Centerline North-South Trail Road 5 - Stamped 2" Alum. Cap on 5/8" x 6' long rebar. N44°E 71.40' to set Nail & Tag in NW side 12" R. Pine N78°E 83.95' to set Nail & Tag in N. side 11" R. Pine N80°W 20.01' to set Nail & Tag in N. side 4" Cherry S34°E 17.06' to set Nail & Tag in NE side 7" Cherry Set Blue Carsonite Post 1' SE

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 9/10/2007

