

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 22 N. R. 12 W. ●	K-5; L-5
2. PROPERTY CONTROLLING IN SECTION 13 _____	T. 22 N. R. 12 W. ●	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W. ●	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Jan. 14, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- K-5 Re-established N.W. Cor. Sec. 13 on straight line & double the distance across found 1/16 cor. & 1/4 cor. to East, which fits one 1957 Road Comm. Wit.
 - L-5 Fd. 1" pipe in "T" Road intersection (B.Top E&W and gravel N.) which fits one Co. rd. Comm. Wit.
 - 1 Fd. 1" bolt w/nut in B.Top Rd. which fits three old Wit. by N. Sageman, Co. Rd. Comm.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


K-5	L-5	1
Set 1 1/4" Iron Rod	Fd. 1" pipe	Fd. 1" Bolt, w/nut
10" Maple S13°E 45.68	P.Pole N63°W 37.37	P.Pole N 2°E 25.27
18" Maple S39°W 44.68	16" Maple S16°W 49.50	Fn.Cor.Post N47°W 50.03
12" Maple S62°W 71.61	14" Maple S37°W 50.17	N.End pipe Hand Rail
Set Ced.post w/Loc. Tag	Ctr. E-W B.Top Rd.	S70°W 66.22
Due S 33'	Due S. 2.3	Ctr. E-W B.Top Rd. Due N. 2.0
Ctr. E-W B.Top Rd	Set Ced.post w/Loc. tag	Set Ced.post w/Loc.tag
DueN. 2.3	Due S 33'	Due S 30
	Old fence to South	
	Due W 1.5	DATE

SIGNED BY Carl F. Roser 4-19-78
 SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SLAGLE TOWNSHIP
 WEXFORD COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____