

SURVEY & INSTRUMENTAL

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1995 DEC 14 PM 3:50

*Linda Dougherty*  
WEXFORD COUNTY, MI  
REGISTERED DEEDS

For corners in Wexford Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T	<u>22N</u>	R	<u>10W</u>	<u>M-2</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, George D. Smith, in a field survey on August 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1837 GLO Quarter Section post by John Brink, Deputy Surveyor, Hemlock 10 S5°W 39, Sugar 10, N 39° W 47  
 1901 D.E. Teed Survey for Petition (Liber 1, Page 171) found remains of both Government wit and spot where stake had been pulled up. Elm 5 S53W64  
 1907 D.E. Teed Survey (Liber 1, Page 124) corner found no desc. or witnesses given  
 W.C.R.C. (no date given) witnesses no date or description given, 3" maple S47°W 47.80', FP N 01°E 26.60'; (old witness book) NE Corner Grange Hall Corner 68.80'  
 1988 Taylor, PS# 32342 Certificate of Survey, Liber 72, Pages 274-275, set 5/8 iron with cap.  
 1988 Taylor, PS# 32342 L.C.R.C., Liber 4, Page 11, Found no evidence of orig. or subsequent monumentation, Set 5/8" Rod with cap #32342 by single proportionate measurement. This location falls opposite a fallen fence line to West and is appx. 1/2' East of a road centerline, 24" Maple S 30° E 78.07', 14" Cherry N 75° E. 94.41' 8" S. Pine N80°W 44.49' Tele Riser box East 25.9', Tele Riser box West 37.8'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 5/8" Iron and Cap #32342 ± 1' East of centerline North-South Road and opposite fence line to West. Position matches 1907 D.E. Deed's Record of Survey distances and with occupation in the Northeast 1/4 of Section 1, T22N, R10W as set by 1901 D.E. Teed's Record of Survey. This corner is accepted as a careful and faithful re-establishment of the position of the original corner, being the quarter corner common to Section 1, T22N, R10W and Section 6, T22N, R9W.

Peer Group Reviewed and Approved

Date: 8 Dec 1995  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" x 36" iron with Wexford County brass cap stamped E 1/4 1, 1995 PS 39098 in mon. box  
 N 40° W 64.97' 8" Scotch Pine  
 S 30° E 78.35' 36" Maple  
 N 69° W 44.96' 12" Scotch Pine  
 S 39° W 69.83', 8" Red Pine



Signed by George D. Smith Date 12-8-95  
Surveyor's Michigan License No. 39098