

APR 16 1999

RECEIVED

1998 DEC 30 AM 10:18

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

For corners in

WEXFORD  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 12W

M-3

2. Property Controlling  
in Section

S \_\_\_\_\_  
S \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_  
S \_\_\_\_\_

*Common to!*  
*A-3 T22N, R11W*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, CRAIG J. PULLEN, PS, in a field survey on OCTOBER 15, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-3 1838 G.L.O. SURVEY BY J. BRINK, WOOD POST, BEECH 8 S53 1/2W 23, BEECH 10 N45 1/2W 33
- 1904 A.J. TEED, SURVEY IN SECTION 1, T22N, R12W, FOUND 3 GOV. WIT., SUGAR 12 S84°E 25 SKEELS STAKE SETS N ABOUT 3R & W ABOUT 2R. DISTANCE TO EAST 1/4 CORNER OF SECTION 1, T22N, R12W IS SHOWN AS 2643.96'
- 1986 USFS SURVEY IN SECTION 1, T22N, R12W, LIBER 2, PAGE 191 AND L.C.R.C. LIBER 3, PAGE 388 BY R. MITCHELL, PS #26417. FOUND 3"X3"X11" REMAINS OF HARDWOOD STAKE 16" BELOW GROUND SURFACE & ACCEPTED AS CORNER PERPUATED BY TEED IN 1904, WHO HAD 3 GOV'T BT'S. FITS GLO CALL FOR SUMMIT OF HILL TO EAST BY 10' +/-, ON OLD DOWN FENCE LINE EAST & WEST. REMONUMENTED CORNER WITH STD. USFS 60" CONC. MONUMENT W/BRASS CAP. S33°E 8" RED PINE 37.62'. N50°E 8" MAPLE 34.18', N6°E 5" MAPLE 18.90', N86°W 34" MAPLE 21.52'
- 1995 WILCOX ASSOCIATES SURVEYS IN SECTION 12, T22N, R12W BY J. D. GEERS, PS #33977, LIBER 74, PAGES 103 & 111, USFS MON. N86°W 21.52' 36" TWIN MAPLE W/NAIL, N06°E 18.90' 5" MAPLE W/NAIL, N50°E 34.18' 14" MAPLE W/NAIL, S33°E 37.62' 8" RED PINE. DISTANCE TO THE EAST 1/4 CORNER SHOWN AS 2640.30'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-3 FOUND USFS BRASS CAPPED CONCRETE MONUMENT IN GOOD CONDITION AND ALL 4 USFS WITNESSES. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3 SECTION CORNER COMMON TO SECTIONS 1 & 12, T22N, R12W AND SECTIONS 6 & 7, T22N, R11W  
5" X 60" SQUARE CONCRETE MONUMENT & BRASS CAP ESTABLISHED: 1986, RLS, 28417, T22N, R12W, 1, 12, T22N, R11W, 6, 7  
N86°W 42" MAPLE 21.47' (USFS)  
N06°E 7" MAPLE 18.95' (USFS)  
N50°E 12" MAPLE 34.18' (USFS)  
N33°E 9" RED PINE 37.58' (USFS)



Peer Group Reviewed and Approved  
Date: 19 Aug 98  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

Signed by *Craig J. Pullen*

Date November 6, 1998

Surveyor's Michigan License No. 39095