

APR 16 1999

RECEIVED

1998 DEC 30 AM 10:19

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Doughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

WEXFORD
(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 12W

M-11

Common to:

2. Property Controlling
in Section

S_

S_

3. Miscellaneous
Property in Sec.

S_

S_

A-11 T22N, R11W

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CRAIG J. PULLEN, PS, in a field survey on NOVEMBER 24, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11 1838 G.L.O. SURVEY BY J. BRINK WOOD POST BEECH 11 S79W 35 BEECH 12 N22W 44

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 SET 5/8" X 36" IRON AND BRASS CAP BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN THE SE CORNER OF SECTION 36 AND THE NE CORNER OF SECTION 24, T22N, R12W. THE CORNER FALLS ON EASTERLY HILLSIDE AND IN CENTERLINE OF OLD NORTH-SOUTH ROAD GRADE. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 SECTION CORNER COMMON TO SECTIONS 25 & 36, T22N, R12W AND SECTIONS 30 & 31, T22N, R11W
5/8" X 36" IRON & BRASS CAP STAMPED: CJP, 1998, 25, 36, 30, 31, 39095

- N46°E 12" BEECH 17.72'
- S58°E 12" BEECH 42.98'
- S8°W 9" BEECH 24.04'
- N80°W 9" TWIN MAPLE 7.75'

Peer Group Reviewed and Approved
Date: 19 Dec 98
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor



Signed by *Craig J. Pullen* Date December 3, 1998

Surveyor's Michigan License No. 39095 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971