

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1995 DEC 14 PM 3:50
RECEIVED

Linda Doughmiller
1995 DEC 14 PM 3:50
WEXFORD COUNTY, MI
REGISTERED DEEDS
Linda Doughmiller
WEXFORD COUNTY, MI
REGISTERED DEEDS

For corners in Wexford Located In: _____ Corner Code # _____
(County)

- 1. Public Land Survey T 22NR 11W M-2
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, George D. Smith, in a field survey on October 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Quarter Section post by John Brink, Deputy Surveyor, Sugar 8 S 70 1/2° W 36, Sugar N 13° W 23
1893 Devoe Survey, Liber 1, Page 175, Survey for Petition in Section 6, T22N-R10W, Corner found no description given, Sugar 12 S 70 1/2° W 36, Sugar 10 S 50° E 56'
1949 MSHD project 83-23' found rotted stake flat in bottom of hole, set 1" axle shaft with gear corner from 2-1" pipes found West along 1/4 line, used pipes for line, set 1/4 corner 33' West from fence found on East line of Road at 1/4 location. 15" Elm S 52° W 66.95', 16" Elm N 27° W 72.21', 10" Elm S 53° E 64.01'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" axle shaft with gear ± centerline road opposite fence line East, location matches 1893 Devoe record of Survey distances between West 1/4 and Southwest corner Section 6, T22N-R10W within 3 feet. This location is accepted as a careful and faithful perpetuation of the position of the original corner, being the quarter corner common to Section 1, T22N, R11W and Section 6, T22N, R10W.

Peer Group Reviewed and Approved

Date: 8 Dec 95
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced axle shaft with 5/8" x 36" iron with Wexford County brass cap stamped E 1/4 1, 1995 PS 39098
S 67° E 66.59' 4" Oak
S 65° W 48.49' 6" Basswood
N 89° W 36.91' 6" Ironwood
N 26° E 69.40', Power Pole with tele. riser



Signed by George D. Smith
Surveyor's Michigan License No. 39098

Date 12-8-95