

JAN 17 1995

COMMISSION

RECEIVED

LAND CORNER RECORDATION CERTIFICATE

1995 DEC 13 AM 11:42

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in WEXFORD

Linda Loughmiller  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>11W</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

CRAIG J. PULLEN

OCTOBER 31

95

I, CRAIG J. PULLEN, in a field survey on OCTOBER 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-5 1837 ORIGINAL G.L.O. SURVEY BY J. BRINK WOOD POST SUGAR 10 S70½W 46 SUGAR 12 N76W 41
- 1913 E.E. SOURS SURVEY IN SEC.18, T22N, R10W FOUND CORNER R.R. IRON FENCE POST S44½W 46' FENCE POST N44W 46'
- 1965 WEXFORD COUNTY ROAD COMMISSION BOOK 2½" PIPE 6" QUAD ELM S45°W 51.50' FENCE COR. N45°E 45.20' FENCE COR. N45°W 53.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-5 FOUND 2½" PIPE IN CENTERLINE 25 ROAD AND CENTERLINE 30 ROAD AND REMAINS OF FENCE POST S44½W 46' (1913 WITNESS). REPLACED PIPE WITH 5/8" X 36" IRON WITH BRASS CAP. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved

Date: 8 Dec 95  
Richard D. Wilcox  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5 SECTION CORNER COMMON TO SECTIONS 12 AND 13, T22N, R11W AND SECTIONS 7 AND 18, T22N, R10W
- 5/8" X 36" IRON AND BRASS CAP STAMPED: CJP, 39095, 12, 13, 18, 7, 1995
- N47°W 4" STEEL FENCE POST CORNER 57.34'
- S35°W TOP CENTER TELEPHONE PEDESTAL 61.69'
- S11°E POWER POLE 98.43'
- N82°E YIELD SIGN POST 52.63'



DECEMBER 6, 1995

Signed by Craig J. Pullen Date \_\_\_\_\_  
Surveyor's Michigan License No. 39095