

JAN 17 1996

RECEIVED

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1995 DEC 21 AM 9:46

For corners in WEXFORD

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Located In: Corner Code #

Table with 3 columns: Description, Located In (T, R, S, T, R, S, T, R), and Corner Code # (M-6)

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

CRAIG J. PULLEN in a field survey on DECEMBER 1, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 1837 ORIGINAL G.L.O. SURVEY BY J. BRINK WOOD POST BEECH 12 S27W 26 BEECH 10 N26 1/2 W 23
1913 E. E. SOURS SURVEY IN SEC.18, T22N, R10W SET QTR. POST MAPLE 10 S70°E'50 MAPLE 9 N48°E 53.5'

Peer Group Reviewed and Approved

Date: Dec 8, 1995
Richard D. Wilcox, Wexford County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 FOUND THE 2 MAPLE WITNESSES TO EAST FROM E. E. SOURS 1913 NOTES. CROSSED THE 2 DISTANCES AND MADE MARK, WHICH FELL 3' WEST OF THE CENTERLINE OF 25 ROAD. THIS POSITION FITS CENTERLINE OF OLD ROAD TO EAST. FOUND 2 FENCES RUNNING EAST ON BOTH SIDES OF OLD ROAD. THE SPLIT OF THE DISTANCE BETWEEN FENCES FELL ON CENTERLINE AND IN LINE WITH THIS POSITION. THERE IS A FENCE RUNNING WEST THAT IS 7' NORTH OF THIS POSITION. THIS POINT WAS ALSO 0.2' FROM BEING EQUIDISTANT FROM SECTION CORNERS TO SOUTH AND NORTH. DUG HOLE AT THIS LOCATION THROUGH 2 ROAD BEDS INTO ORIGINAL DARK SOIL. FOUND VERTICALLY ORIENTED WOOD FIBERS AND ROUND STONE 3.5' DOWN. THIS EVIDENCE WAS ACCEPTED AS E. E. SOURS 1913 1/4 CORNER. SET 5/8" X 36" IRON IN WOOD REMAINS AND EQUIDISTANT FROM SECTION CORNERS TO SOUTH AND NORTH. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 1/4 CORNER COMMON TO SECTION 13, T22N, R11W AND SECTION 18, T22N, R10W
5/8" X 36" IRON AND BRASS CAP STAMPED: CJP, 39095, 1995, 1/4 18, 13
S69°E 36" MAPLE 50.55'
N49°E 30" MAPLE 53.65'
N79°W CORNER FENCE POST 35.36'
S29°E 18" TWIN CHERRY 89.03'



Signed by Craig J. Pullen

Date DECEMBER 8, 1995

Surveyor's Michigan License No. 39095