

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1995 DEC 13 AM 11:42

For corners in  
WEXFORD

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	22N	R	11W	M-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

*Linda Doughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CRAIG J. PULLEN, in a field survey on OCTOBER 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-9 1837 ORIGINAL GOVERNMENT SURVEY BY J. BRINK WOOD POST BEECH 11 S28½W 48 BEECH 14 N53W 29 1901 H.J. DEVOE SURVEY IN SEC.30, T22N, R10W ORIGINAL GOVERNMENT CORNER WITH STONE & CROCKERY AROUND POST IN CENTER OF HIGHWAY.  
WEXFORD COUNTY ROAD COMMISSION OLD WITNESS BOOK IRON PIN (MON.BOX) COR. F.P. NW 31.60' COR. F.P. SW 41.20' COR. F.P. SE 44.20'  
1978  
& 1988 J.L. WILCOX & ASSOC. SURVEY L. 1, P. 620, AND L. 66, P.510, RESPECTIVELY & L.C.R.C. L. 3, P. 176 BY J.L. WILCOX, PS #14102 FOUND 1½" PIN IN MONUMENT BOX AT INTERSECTION N30°W 20" MAPLE 46.47' N50°E 6" W. PINE 53.26' S40°E 24" MAPLE 68.03' S60°E 24" MAPLE 69.62'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 FOUND 1½" IRON IN MONUMENT BOX IN CENTERLINE 34 ROAD AND 6' WEST OF CENTERLINE OF 25 ROAD, AND THREE PREVIOUS WITNESSES. REPLACED 1½" IRON WITH 5/8" X 36" IRON AND BRASS CAP. THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved  
Date: 22 Nov 95  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 SECTION CORNER COMMON TO SECTIONS 24 AND 25, T22N, R11W AND SECTIONS 19 AND 30, T22N, R10W  
5/8" X 36" IRON AND BRASS CAP STAMPED: CJP, 39095, 1995, 24, 25, 19, 30  
N30°W 24" MAPLE 46.47'  
S28°W POWER POLE 83.25'  
S60°E 32" MAPLE 69.31'  
N50°E 12" WHITE PINE 53.23'



Signed by Craig J. Pullen Date NOVEMBER 9, 1995  
Surveyor's Michigan License No. 39095