

JAN 17 1996

RECEIVED

1995 DEC 13 AM 11:42

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
WEXFORD

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>11W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CRAIG J. PULLEN, in a field survey on OCTOBER 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-12 1837 ORIGINAL GOVERNMENT SURVEY BY J. BRINK WOOD POST SUGAR 7 N24½W 8 SUGAR 14 S11W 30
- 1900 D.E. TEED SURVEY IN SEC.31, T22N, R10W FOUND IRON STAKE AND WIT. SET BY DEVOE SUGAR 24 S30°E 82 (DATE OF SURVEY UNKNOWN).
- 1901 TEED'S NOTES COPIED FROM H.J. DEVOE SURVEY IN SEC.30, T22N, R10W, (DATE UNKNOWN) ORIGINAL GOVERNMENT POST MADE OF HICKORY WITH STONE & CROCKERY. IRON POST WITH GOV. WITNESS.
- 1971 WEXFORD COUNTY ROAD COMMISSION BOOK J. SWITALSKI 10" PINE N45°E 75.50' 18" MAPLE S45°E 110.20' F.P. W 36.90'
- 1988 J.L. WILCOX & ASSOC. SURVEY BY D. SCHRIPEMA, PS #24617 FOUND 1½" PIPE S85°E 29.08' 6" CHERRY S10°E 105.21' POWER POLE N50°E 75.92' 20" R. PINE S85°W 37.49' FENCE POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-12 FOUND 1½" PIPE 4' EAST OF CENTERLINE 25 ROAD AND IN LINE WITH E-W FENCES, AND 3 PREVIOUS WITNESSES. REPLACED PIPE WITH 5/8" X 36" IRON AND BRASS CAP. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved

Date: 22 Nov 95
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12 ¼ CORNER COMMON TO SECTION 36, T22N, R11W AND SECTION 31, T22N, R10W
- 5/8" X 36" IRON AND BRASS CAP STAMPED: CJP, 39095, 1995, ¼, 31, 36
- S85°E 8" CHERRY 29.08'
- S10°E POWER POLE 105.21'
- N50°E 20" RED PINE 75.98'
- S83°W TOP CENTER OF TELEPHONE PEDESTAL 32.69'



Signed by Craig J. Pullen
 Surveyor's Michigan License No. 39095

Date NOVEMBER 9, 1995