

CLEARLY
SURVEYED

RECEIVED

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE

1995 DEC 13 AM 11:42

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
WEXFORD

Linda Longmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>11W</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, CRAIG J. PULLEN, in a field survey on OCTOBER 23, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-13 1837 ORIGINAL G.L.O. SURVEY BY J. BRINK WOOD POST SUGAR 12 N10W 20 HEMLOCK 12 S70½E 30
- 1900 D.E. TEED SURVEY IN SEC.31, T22N, R10W, FOUND STONE WITNESSES GONE SUGAR 24 S28½W 68
- 1902 H.J. DEVOE SURVEY IN SEC.6, T21N, R10W A LARGE STONE ROLLED IN PIT, UPPER PART POINTED AND CROSS + MARKED. PLACED THERE BY H.J. DEVOE SOME YEARS SINCE AT GOV. POINT.
- 1971 WEXFORD COUNTY ROAD COMMISSION BOOK. STONE WITH CHAIN AROUND IT P.P. N50°W 59.30' 8" APPLE S75°W 93.20' 10" CEDAR S75°E 98.70'
- 1986 J. L. WILCOX, PS #14102 L.C.R.C. L.3, P.407 FOUND ½" IRON IN CENTERLINE ROADS N-S AND E-W S72°W 10" APPLE 93.70' N45°W COR. FE. POST 48.69' N45°E COR. FE. POST 47.04' S72°E 12" CEDAR 99.38'
- 1988 WADE-TRIM/GRANGER SURVEY L.67, P.459 BY J. RAY, PS #25869 FOUND NAIL IN HOLE IN ASPHALT S55°W STOP SIGN 49.80' N50°W FE. POST 48.67' N45°E FE. POST 47.10' EAST PHY. CENTERLINE RD. 0.80'
- 1993 J. RAY, PS #25869 L.C.R.C. L.4, P.154 FOUND NAIL IN HOLE IN BIT. AT CENTERLINE INT. OF 25 RD. AND 38 RD. S71°E 18" CEDAR 99.31' S55°W STOP SIGN 49.80' N45°E FE. POST 47.10' N50°W FE. POST 48.67'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 FOUND ½" IRON WITH SPIKE NAIL IN TOP AND CHAIN WRAPPED AROUND BOTTOM IN INTERSECTION OF 25 ROAD AND 38 ROAD. REPLACED WITH 5/8" X 36" IRON AND BRASS CAP. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved

Date: 22 Nov 95

Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 TOWNSHIP CORNER COMMON TO SECTION 36, T22N, R11W, SECTION 1, T21N, R11W, SECTION 31, T22N, R10W, AND SECTION 6, T21N, R10W
5/8" X 36" IRON WITH BRASS CAP STAMPED: CJP, 39095, 1995, 36, 1, 6, 31
N48°W POWER POLE 59.65'
S72°W 10" APPLE 93.70'
S72°E 18" CEDAR 99.31'
N45°E CORNER FENCE POST 47.10'

Signed by Craig J. Pullen

Date NOVEMBER 9, 1995

Surveyor's Michigan License No. 39095