

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>23</u> N. <u>9</u> W.		G-10 H-9 G-11 H-11
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 12-7 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, ~~found, recovered, restored, established or re-established as expressed below~~ and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-10 Accepted corner as used by Finnerty and recovered by Wilcox & Erickson.
- G-11 Accepted axle shaft as used by Finnerty.
- H-9 Accepted old corner of record as recovered by Wilcox & Erickson.
- H-11 Reestablished corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10	G-11	H-9	H-11
Fd. 3/4" iron rod.	Fd. Axle Shaft	Fd. 3/8" iron buried in E-W	Set DNR Mon & Cedar GD Post
Wit. & Rec. by Wilcox & Erickson 5-15-72	12" R.Pine S60°E 17.48 (side nail)	Co. Road Cor.Mon Due S 33'	6" Maple N59E 38.7
	6" Map. N80E 55.70 (side nail)	Wit. & Rec. by Wilcox & Erickson 5-15-72	6" Oak N55W 25.3
	Ctr.US-131 Pavt. N50W 38'		8" Maple Due W54.7
			4" Oak N26W 33.8
			Rand.E-W Due S 25'

SIGNED BY Carl F. Roser DATE 1-11-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

