

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>23</u> N. <u>9</u> R. <u>9</u> W.	J-9      K-10 K-9      K-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 10-25 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-9      Recovered "Teed" corner of record.
- K-9      Recovered "Teed" corner of record. Teed had Govt. Witness here.
- K-10     Recovered "Teed" corner of record which = Govt. corner.
- K-11     Restored corner per U.S.B.T. stump, Y. Pine showing lower face.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9	K-9	K-10	K-11
Fd. 1"x24" pipe (Teed)	Fd 1 1/4"x16" King	Set DNR Mon &	Set DNR Mon & Cedar
Added DNR Mon.	Pin (Teed)	Maple Gd Post	Guard Post
14" Oak N13E 68.3'	18" Oak N49E 70.7'	12" Oak N80W 34.8'	20" R.Pine N 9E 28.7'
18" Oak N52E 96.7'	8" Oak S76E 20.3'	8" Oak N47E 21.7'	3" R.Pine S26E 14.5'
10" TwOak S21E 24.5'	12" Oak S 8W 27.9'	4" R.PineS42E 40.2'	10" RP stp S84W 25.7'
Set Ced Post w/loc tag	Set Ced Post	US Wit Blaze Notch	4" R.Pine S53E 58.2'
Due N 16.5'	Due S16.5'	Y.P.Stp 15" S35W 11.0'	(Y.P.stp N47W 11.2'
	Ctr Trl N Due E 6'	N-S Rand Due W 26'	(U.S.Wit.15")
	Ctr E-W Trl Due N 2'		N-S Rand Due W 32'


SIGNED BY Carl F. Roser DATE 1-11-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_