

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
WEXFORD
 (County)

Located in:

Corner Code #

		23N	9W	D-13
1. Public Land Survey	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
2. Property Controlling In Section	S	_____	T	_____
	S	_____	T	_____
	S	_____	T	_____
3. Miscellaneous Property in Section	S	_____	T	_____
	S	_____	T	_____
4. Lot No. _____, Recorded Plat _____				
5. Private Claims _____				

RECEIVED

1996 OCT -9 PM 3: 27

Linda Loughmiller
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, CRAIG J. PULLEN, in a field survey on MAY 31, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13 1838 ORIGINAL GLO SURVEY BY J. BRINK WOOD POST Y. PINE 13 N16W 13 BEECH 11 N32W 19
- 1881 A.J. TEED SURVEY IN SEC.32, T23N, R9W CORNER SHOWN AS IN NO WITNESSES GIVEN
- 1993 GRAND TRAVERSE SURVEYING CO. SURVEY IN SEC.32, T23N, R9W L.72, P.777 NEIL WAY, PS #28432 SET 1/2" IRON & CAP MIDWAY AND ON LINE IN EAST-WEST FENCE 3" W. PINE NORTH 22.60' 2" OAK N5°W 12.10' 18" POPLAR N50°W 31.65'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-13 FOUND 1/2" IRON WITH CAP #31611 IN EAST-WEST FENCE REMAINS AND 2 PREVIOUS WITNESSES. REPLACED 1/2" IRON WITH 5/8" X 36" IRON AND BRASS CAP. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &
 MONUMENTATION

MAY 20 1997


COMMISSION

Peer Group Reviewed and Approved

Date: 26 Sep 96
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13 1/4 CORNER COMMON TO SECTION 32, T23N, R9W, AND SECTION 5, T22N, R9W
- 5/8" X 36" IRON AND BRASS CAP STAMPED: CJP, 39095, 1996, 32, 5, 1/4
- NORTH 3" WHITE PINE 22.60'
- N5°W 2" OAK 12.10'
- N50°W 16" POPLAR 45.55'
- N25°E 5" MAPLE 30.24'



SEPTEMBER 9, 1996

Signed by Craig J. Pullen Date _____
 Surveyor's Michigan License No. 39095