

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**WEXFORD**

(County)

Located in:

Corner Code #

		23N		9W	J-13
1. Public Land Survey	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

**RECEIVED**

1996 OCT -9 PM 3: 27

*Linda Loughmiller*  
**WEXFORD COUNTY, MI**  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CRAIG J. PULLEN, in a field survey on JULY 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- J-13 1838 ORIGINAL GLO SURVEY BY J. BRINK WOOD POST BEECH 10 N7½E 26 Y. PINE 12 N5½W 26
- 1901 D.E. TEED SURVEY IN SEC.2, T22N, R9W FOUND Y. PINE NW OK W. PINE 18 N58¾W 20 W. PINE 20 S39¼W 29½
- 1927 C.E. STACKUS SURVEY IN SEC.2, T22N, R9W FOUND BOTH OLD GOV'T BEARING STUMPS W. PINE N59W 20 W. PINE S39W 29½
- 1958 MICH. DEPT. OF CONSERVATION SURVEY IN SEC.2, T22N, R9W BY K. OSTLING, PS #10068 FOUND WHAT I BELIEVE TO BE THE GOVERNMENT CORNER AS PREVIOUSLY LOCATED AND RECORDED BY DELMAR TEED IN 1901 AND C.E. STACKUS IN 1927. FOUND DEFINITE STAKE POINT AT CORNER, A W. PINE STUMP 18 N58W 20 AND A W. PINE STUMP 20 S39W 29½ FOR TEED'S BT'S. THE OBT STUMP, A Y. PINE 12 N5½W 28 IN PLACE WITH POSSIBLE FACE CHECKS GOOD WITH SWAMP EDGE WEST. SET 1" PIPE WITH 4" BRASS CAP 14" R. PINE S60°W 208 LKS 14" B. OAK S28°E 53½ LKS

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

J-13 FOUND 1" PIPE WITH ALUMINUM DNR CAP IN GOOD CONDITION, 1 PREVIOUS WITNESS, AND CEDAR LOCATION POST 1' SOUTHWESTERLY. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &  
 MONUMENTATION

MAY 20 1997


Peer Group Reviewed and Approved

Date: 26 Sep 96

*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- J-13 ¼ CORNER COMMON TO SECTION 35, T23N, R9W, AND SECTION 2, T22N, R9W
- 1" PIPE WITH ALUMINUM DNR CAP
- S28°E 26" RED OAK 35.64'
- S42°E 9" WHITE OAK 34.33'
- N72°W 4" WHITE OAK 20.24'
- N58°E 4" WHITE PINE 22.94'



Signed by Craig J. Pullen Date SEPTEMBER 9, 1996  
 Surveyor's Michigan License No. 39095