

MAR 8 1 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 9:42

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 23N R 9W M-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-1) 1837 GLO Section post by John Brink, Deputy Surveyor, Hemlock 11 N 58 1/2° E 30 links, Hemlock 10 N 66 1/2° W 25 links
- M-1) 1892 A. Teed survey, Liber 1, page 232: Found remains of both Hemlock witnesses and old stake, Pine 40 N 10° E 42 1/2 links
- M-1) 1896 A. Teed survey, Liber 1, page 338: Found stake
- M-1) 1905 D. Teed survey, Liber 1, page 339: Found stake, W. Pine 8 S 20°W 72, Elm 2 S 33°W 52
- M-1) 1973 Wilcox survey, Liber 2, page 602: Found pk-nail set Wexford Co. monument in centerline of roads North-South and East-West, N 25° W 58.75, 5" Birch S 30° W 37.09, 20" W. Pine S 60° E 86.23, 6" B. Spruce
- M-1) 1979 Wilcox survey in Section 36, T23N, R8W, Liber S-1, page 478: Found Wexford Co. monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-1) Northeast corner Section 1: Found Wexford County monument (top missing) ±2' West of centerline of North-South road and in centerline of East-West road. This corner is accepted as a careful perpetuation of the position of the original corner.


Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-1) Set 5/8" x 36" Iron with Wexford County brass cap stamped: NE cor. 1, PS 33989, 1993

- N 25° W - 57.20 - 6" Cedar
- N 40° E - 54.77 - 9" Poplar
- S 52° E - 74.06 - 7" White Pine
- S 18° E - 44.95 - 10" Poplar
- S 31° E - 37.74 - 24" White Pine



Signed by Richard D. Wilcox Date 11/29/93

Surveyor's Michigan License No. 33989