

SURVEY &  
RECORDATION

MAR 3 1 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 9:43

For corners in

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Wexford  
(County)

Located In:

Corner Code #

- |                                    |   |            |   |           |            |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey              | T | <u>23N</u> | R | <u>9W</u> | <u>M-2</u> |
|                                    | T |            | R |           |            |
|                                    | T |            | R |           |            |
|                                    | T |            | R |           |            |
| 2. Property Controlling in Section | S |            | T | R         |            |
|                                    | S |            | T | R         |            |
| 3. Miscellaneous Property in Sec.  | S |            | T | R         |            |
|                                    | S |            | T | R         |            |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-2) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor, Elm 8 N 25°W 35 links, Beech N 57° W 18 links
- M-2) 1892 Teed survey, Liber 1, page 232: Found stake and stone (Sugar 8 S 49°W 73, Sugar N 75 1/2° W 61 1/2, BC Bonnell 1878).
- M-2) Wilcox survey, Liber 1, page 120, also Liber 2, page 604: Set Wexford County monument in centerline of North-South and West roads, set by single proportionate measure between NE corner and SE corner and by occupation East and West
- M-2) 1979 Wilcox survey in Section 6, T23N, R8W, Liber S-1, page 478: Found Wexford County monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-2) 1/4 Section corner common to Section 1, T23N, R9W and Section 6, T23N, R8W

Found 1/2 Iron and cap ±6' North of centerline of road to West, 2' East of North-South road opposite old fence line East. Corner fits one old witness from Liber 2, page 604. This corner is accepted as a careful and faithful perpetuation of the original corner.

Peer Group Reviewed and Approved


Date: 11-29-93

*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-2) Set 5/8" x 36" Iron with Wexford County brass cap stamped: E 1/4 1, PS 33989, 1993

- N 53° E - 56.48 - 7" Jack Pine
- N 54° W - 59.23 - 7" Jack Pine
- S 66° W - 62.43 - 4" Apple
- S 12° E - 85.48 - 4" Jack Pine



Signed by *Richard D. Wilcox* Date 11/29/93

Surveyor's Michigan License No. 33989