

MAR 8 1 1984

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 9:43

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 23N R 9W M-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

A. Description of original monument and accessories and/or subsequent restoration:

- M-3) 1837 GLO Section post by John Brink, Deputy Surveyor, Hemlock 18° S 42° W 16 links, Hemlock 24° N 50° W 64 links
- M-3) 1892 A. Teed survey, Liber 1, page 232, corner graded out, found roots of Hemlock wit., Hemlock 30 S 74 1/2° W 7 1/2 links
- M-3) 1894 A. Teed survey, Liber 1, page 252, big stake in road
- M-3) 1973 Wilcox survey, Liber 2, page 600, set Wexford Co. monument in East edge of North-South road and centerline road to West. Set by single proportionate measure North and South and by occupation East and Wwest
- M-3) 1979 Wilcox survey in Section 6, T23N, R8W, Liber S-1, page 478, Found Wexford Co. monument
- M-3) 1985 Wilcox survey in Section 7: Liber S-2, page 226, Found Wexford Co. monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-3) Section corner common to Sections 1 and 12, T23N, R9W and Sections 6 and 7, T22N, R8W

Found Wexford County monument (w/ top missing) in centerline of road to West and 7' East of centerline of a North-South road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3) Set 5/8" x 36" Iron with Wexford County brass cap stamped: SE 1, PS 33989, 1993

N 13° E - 41.16 - 6" Elm
S 63° W - 66.47 - Power pole
S 17° E - 11.25 - 8" Elm
S 33° W - 64.80 - 20" Maple



Signed by *Richard D. Wilcox*

Date 11/29/93

Surveyor's Michigan License No. 33989